



#### NOTES:

1. IF REQUIRED, TRANSVERSE JOINTS TO BE INSTALLED AT NO GREATER THAN 50 METRE CENTRES AND SHALL EXTEND THE FULL WIDTH OF THE FOOTWAY.
2. IN THE CASE OF THE INSTALLATION OF NATURAL STONE PAVING A MINIMUM PSV OF 55 IS REQUIRED, AND PROVIDED WITH A BUSH HAMMER OR FLAME FINISH.
3. FOR ALTERNATIVES FOOTWAY CONSTRUCTION REFER TO NTA-TCD-1100-015, 016 AND 018.
4. FOR KERB CONSTRUCTION DETAILS REFER TO NTA-TCD-1100-011.
5. ALL CONCRETE TO COMPLY TO IS EN 206.
6. FOR FURTHER DETAILS ON MATERIALS AND SPECIFICATION REFER TO DMURS ADVICE NOTE 2.
7. PRECAST PAVING SLABS TO BS EN 1339:2003.
8. ADDITIONAL LAYER BELOW OF 100mm MINIMUM UGM Ac REQUIRED AT VEHICULAR ACCESSSES.
9. WHERE VERGE IS PRESENT CONSIDERATION SHOULD BE GIVEN TO FALL FOOTWAY TO VERGE.
10. FOOTWAY DESIGN TO BE AGREED WITH THE CONTRACTING AUTHORITY.
11. ALL DIMENSIONS IN MILLIMETRES U.N.O.

NOT TO SCALE

### TYPICAL CONSTRUCTION DETAILS

Series:

NTA-1100: KERBS, FOOTWAYS AND PAVED AREAS

Date	Issue
JAN'26	01

Title

PAVED FOOTWAY  
CONSTRUCTION  
(SLABS / FLAGS)

Drawing File Number

NTA-TCD-1100-017



An Roinn Iompair  
Department of Transport

